


A Waterproof*, Protective Skin Is What Makes Dincel Formwork Different.

- NCC Compliant Polymer
- Waterproof Wall Face
 - No Scaffolding
- Lightweight Modular Construction
 - Shop Drawing NOT required
- No Custom Fabrication Leadtimes
 - No Heavy Haulage
 - No Craneage

* As tested by CSIRO




www.dincel.com.au






Precast walls are typically required to be installed prior to wall girts and fascia purlins, hence riggers must come back to the project after the installation of precast walls.

Dincel walls are installed without the need for craneage, allowing the riggers and Dincel wall installers to work simultaneously, eliminating the loss of time associated with precast walls.





Dincel Dado Wall Construction Sequence

- Excavate & pour piles/pad footings for portal frame structure.
- 2. Excavate shallow Dincel Dado wall perimeter trench (in stages).
- 3. Place and brace portal frames.
- 4. Install purlins, wall girts & associated bracing.



Dincel & Precast Dado Wall Installation Comparison

	Components	Heavy Haulage	Lead Times	Footings	Concrete Core Fill	Labour	Reinforcement		Scope	Installation Program
Dincel Structural Walling	Lightweight Modular	No	1-2 Weeks	400 x 400 Trench	Yes Install Crew	2 Men	Vertical Bars Only	SUMMARY	Minimal Lead Time Lightweight Modular Dincel Wall Monolithic Pour With Trench Footing	200m²/Day 2 Man Crew Flat Bed Delivery
Precast Walling	Heavyweight Custom Made	Yes	5 Months Plus	No	Offsite Precasting	Truck/Crane 2 Men	Mesh & Perimeter Bars	SU	Custom Design & Fabrication (Long Lead Times) Heavy Haulage & Crane Packers & Ferrule Connections	110m²/Day (7 Bays) 2 Men/Bay Individual Semi & Crane/Bay



5. Place and temporary brace Dincel walls, directly after wall girt installation.

6. Pour Dincel Dado walls & footing simultaneously followed by installing wall sheeting.

7. Pour ground slab to face of Dincel walls to suit Engineers details.



• Scan the QR Code for further construction detailing information.

